



Goodwyn Mills Cawood
1906 E Three Notch Street
Andalusia, Alabama 36421
T 334.222.2699

TRANSMITTAL COVER SHEET

DATE: JULY 15, 2025
TO: ALL PLAN HOLDERS
FROM: PATSY STINSON
PROJECT: 50' X 50" BOX HANGAR
SOUTH ALABAMA REGIONAL AIRPORT
COVINGTON COUNTY, AL
GMC PROJECT NO.: TMGM250006
RE: ADDENDUM #1

PLEASE COMPLETE BELOW AND RETURN IMMEDIATELY VIA EMAIL to:

PATSY STINSON
Email: patsy.stinson@gmcnetwork.com

I, the undersigned, hereby acknowledge receipt of Addendum 1.

Authorized Representative

Date

Company Name

ADDENDUM NUMBER 1

50' X 50' BOX HANGAR
SOUTH ALABAMA REGIONAL AIRPORT
COVINGTON COUNTY, AL
GMC PROJECT NO: TMGM250006

I. General

A. The following clarifications, revisions, additions are hereby made a part of same, and shall be incorporated in the Project Manual, Drawings, and Work of the Contract the same as if originally included in the Bid and Construction Documents.

B. Bidders shall acknowledge receipt of this Addendum in writing, as provided on the Transmittal Cover Sheet and the Proposal Form.

C. When a revision and/or addition is called for to the Drawings or Project Manual, they shall be fully coordinated with and carried through all applicable Drawings and portions of the Project Manual, including in part, all related Civil, Landscaping, Architectural, Structural, Electrical, and other Documents.

II. Response to Comments

Q: What R-Value do you want to achieve? Would Vinyl faced blanket insulation be an alternative?

A: We will proceed with spray foam on the hangar roof only and 4" thick insulation with white WMP-50 facing on the exterior walls. The "R" value shall comply with ASHRAE 90.1.

Q: There are several articles sections in the specification referencing temporary closer of the runway. I cannot tell if this is being suggested or will be necessary. Is this something standard in all airport projects or are we thinking sections of the runway are going to be shut down or detoured?

A: There will be no runway closure required for this project.

Q: Is there some type of rolling door? Any specifics on this to pass on to the building manufacturer.

A: Sheet 10 in the plan set has the door opening requirements. The door shall be a manual sliding door on tracks.

III. Conclusion

A. This is the end of Addendum Number 1.