ADDENDUM NO. 1

CITY OF CARTERSVILLE, GEORGIA

Mechanicsville & Jones Mill Rd. Water Main Replacement

BID DATE: November 12, 2026
TIME: 3:00 P.M.

Date: October 28, 2026

ACKNOWLEDGE RECEIPT OF THIS ADDENDUM BY INSERTING ITS NUMBER IN THE BID FORM. THIS ADDENDUM FORMS A PART OF THE PROJECT DOCUMENTS. IT MODIFIES THEM AS FOLLOWS:

QUESTION:

1. The UNCASED bores will be 12IN DIA. which will leave a 2" void under each driveway that may in time collapse or sink down; Is the Owner open to open cut these areas, or placing casing to avoid the possible collapses or sinking?

   Response: We agree a 12" uncased bore is required for an 8" DIP. Since the pipe will be installed at a depth of 42" we are not concerned with the limited void space. Yes, in time the soil will sink but feel it will not be enough to be a detriment to the paved driveways.

2. Regarding the required capping/blocking, we did not see a detail on the plans?

   Response: Pipe will be restrained at the joints called out for in the plans. No additional restraint shall be required.

3. There are at least four areas on the plans that call out for "Clearing & Grubbing" or "Tree Removal," how is this to be paid, there is no line item for either of these items

   Response: If there is no line item on the bid form for work described in the plans then the cost of the work shall be added to another line item that is listed on the Bid Form.

4. There are two different typical street repair details: one with a concrete cap and GAB all the way up, and the other is for GAB, Binder, Topping. Which is correct?

   Response: I only see one "Typical Street Cut Repair" detail (3.8.11) on the plans, see sheet C-901. Use this detail for any asphalt pavement cuts.

END OF ADDENDUM NO. 1